IFC CONTRACTING SOLUTIONS

Insured:	Isbell, Chris	**E-mail:**	
Property:	504 Liberty Ct		
	Colleyville, TX 76034		

Contractor:		**Business:**	(817) 470-2600
Company:	IFC Contracting Solutions		
Business:	5115 Colleyville, TX 76034		

Claim Number: 4391W097S **Policy Number:** 43CYY8688 **Type of Loss:** Wind/ Hail

Date of Loss: 5/6/2025 **Date Received:**

Date Inspected: **Date Entered:** 2026-02-26

Price List: TXDF8X_FEB26

Restoration/Service/Remodel

Estimate: **ISBELL_CHRIS**

IFC Contracting Solutions
ISBELL_CHRIS

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
Dwelling Roof									
1	Tear off, haul and dispose of comp. shingles - Laminated ADJ	76.00	SQ	0.00	0.00	5,209.04	0.00	1,041.81	**6,250.85**
	Our line item 1 covers insurance line item 1. We are requesting 76.0 SQ for tear off, haul and dispose of comp. shingles - Laminated. 1. Per EagleView measured area (no waste applied to tear-off), the correct quantity is 76.0 SQ. Insurance used 75.29 SQ. a. Please see attached EagleView Report confirming the measured square footage for Structure #1.								
2	Laminated - comp. shingle rfg. - w/ out felt ADJ	91.00	SQ	0.00	6,237.14	25,955.93	2,141.36	6,438.61	**40,773.04**
	Our line item 2 covers insurance line item 2. We are requesting 91.0 SQ of Laminated - comp. shingle rfg. - w/out felt. 1. The difference reflects the EagleView suggested waste calculation. Insurance used 90.67 SQ while EagleView suggests 91.0 SQ with 20% waste applied. a. Please see attached EagleView Report for Structure #1 showing the waste calculation of 20% due to the complexity of the roof.								
3	Roofing felt - synthetic underlayment ADJ	91.00	SQ	0.00	0.00	4,783.87	394.67	956.77	**6,135.31**
	Our line item 3 covers insurance line item 3. We are requesting 91.0 SQ of roofing felt - synthetic underlayment. 1. Insurance used 75.29 SQ with no waste applied to the underlayment. EagleView suggests 91.0 SQ with 20% waste for Structure #1. a. Roofing felt, like shingles, must be installed in a staggered and overlapping pattern to ensure proper water shedding and code compliance. During this process, cuts are required at eaves, valleys, hips, ridges, and roof penetrations, which inevitably generates material waste. This waste is a necessary part of achieving a watertight underlayment system. b. Please see attached EagleView Report confirming the 20% waste calculation for Structure #1.								
4	Asphalt starter - universal starter course ADJ	471.00	LF	0.00	0.00	974.97	80.44	194.99	**1,250.40**
	Our line item 4 covers insurance line item 4. We are requesting 471.0 LF of Asphalt starter - universal starter course. 1. The difference is $88.11. Per EagleView, the eaves starter LF for Structure #1 is 471.0 LF. Insurance used 634.37 LF which appears to combine both structures. a. Starter is a distinct roofing component with a separate material profile and a higher associated labor rate compared to field shingles. It should not be bundled into waste calculations. b. Please see attached EagleView Report confirming the 471.0 LF eaves measurement for Structure #1.								
5	R&R Hip / Ridge cap - High profile - composition shingles ADJ	567.42	LF	0.00	1,628.50	4,879.81	402.58	1,301.66	**8,212.55**

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
	Our line item 5 covers insurance line item 5. We are requesting 567.42 LF of R&R Hip / Ridge cap - High profile - composition shingles. 1. Per EagleView Structure #1, ridges = 138.0 LF and hips = 429.42 LF, totaling 567.42 LF. Insurance used 432.05 LF. a. The insured currently has High Profile Ridge cap installed and it must be replaced in kind. Please see attached EagleView Report confirming the ridge and hip measurements for Structure #1.								
6	Ice & water barrier	890.88	SF	0.00	0.00	1,772.85	146.26	354.57	**2,273.68**
7	Roof vent - turbine type	2.00	EA	0.00	0.00	349.54	28.84	69.91	**448.29**
8	Roof vent - turtle type - Metal	6.00	EA	0.00	0.00	471.90	38.93	94.38	**605.21**
9	R&R Exhaust cap - through roof - 6" to 8"	7.00	EA	0.00	0.00	910.28	75.10	182.06	**1,167.44**
10	Prime & paint roof vent	7.00	EA	0.00	0.00	339.22	0.00	67.84	**407.06**
11	R&R Flashing - pipe jack - lead	8.00	EA	0.00	202.88	608.80	50.23	162.34	**1,024.25**
12	Prime & paint roof jack	8.00	EA	0.00	0.00	387.68	0.00	77.54	**465.22**
13	R&R Drip edge ADJ	624.00	LF	0.00	561.60	1,672.32	137.97	446.78	**2,818.67**
	Our line item 13 covers insurance line item 13. We are requesting 624.0 LF of R&R Drip edge for the main house. 1. Per EagleView Structure #1, drip edge LF is 624.0 LF. Insurance used 634.37 LF which appears to combine both structures. a. Please see attached EagleView Report confirming the 624.0 LF drip edge measurement for Structure #1.								
14	Step flashing ADJ	158.83	LF	0.00	0.00	1,948.84	160.78	389.77	**2,499.39**
	Our line item 15 covers insurance line item 15. We are requesting 158.83 LF of Step flashing. 1. Per EagleView Structure #1, step flashing LF is 158.83 LF. Insurance used 158.0 LF. a. Please see attached EagleView Report confirming the step flashing measurement for Structure #1. b. Please see Photo Report showing the hail damage to the existing step flashing.								
15	R&R Counterflashing - Apron flashing	63.00	LF	0.00	0.00	829.08	68.40	165.82	**1,063.30**
16	R&R Valley metal ADDED	297.83	LF	0.00	571.83	1,712.52	141.28	456.87	**2,882.50**
	The insurance report left out the Valley Metal. We are requesting 297.83 LF of R&R Valley metal. 1. Per Xactimate pricing, this costs an additional $2,289.68. a. The insured has closed valleys which require valley metal to be replaced during the re-roof. Valley metal is a separate component from step flashing and cannot be reused once the shingles are torn off. b. Please see attached EagleView Report confirming the 297.83 LF of valleys for Structure #1.								
17	Additional charge for steep roof - greater than 12/12 slope (install) ADDED	91.00	SQ	0.00	0.00	4,689.23	0.00	937.85	**5,627.08**

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
	The insurance report left out the Additional charge for steep roof install. We are requesting 91.0 SQ for the steep roof installation charge. 1. Per Xactimate pricing, this costs an additional $4,689.23. a. The predominant pitch per EagleView is 16/12, which exceeds the 12/12 threshold and requires a steep charge for installation. Workers must use specialized equipment, additional safety measures, and work at a significantly reduced pace on this slope. b. Please see attached EagleView Report confirming the 16/12 pitch for Structure #1.								
18	Additional charge for steep roof - greater than 12/12 slope (removal) ADDED	76.00	SQ	0.00	1,221.32	0.00	0.00	244.26	**1,465.58**
	The insurance report left out the Additional charge for steep roof removal. We are requesting 76.0 SQ for the steep roof removal charge. 1. Per Xactimate pricing, this costs an additional $1,221.32. a. The predominant pitch per EagleView is 16/12, which exceeds the 12/12 threshold. Tear-off on a 16/12 pitch requires additional safety equipment and labor considerations beyond standard slope tear-off. b. Please see attached EagleView Report confirming the 16/12 pitch for Structure #1.								
19	Additional charge for high roof (2 stories or greater) ADDED	91.00	SQ	0.00	594.23	2,227.68	0.00	564.38	**3,386.29**
	The insurance report left out the Additional charge for high roof (2 stories or greater). We are requesting 91.0 SQ for the high roof charge. 1. Per Xactimate pricing, this costs an additional $2,227.68 for install and $593.23 for removal. a. Per EagleView, this structure is greater than 1 story. Laborers must haul materials and equipment to an elevated height, increasing time and safety requirements. b. Please see attached EagleView Report and Photo Report confirming the multi-story height of the structure.								
20	Specialty Work_Dormer (Bid Item) ADDED BID	1.00	EA	0.00	0.00	6,318.00	0.00	1,263.60	**7,581.60**
	The insurance report left out the Dormer specialty work. We are requesting approval of our sub bid. 1. Our sub bid cost is $6,318.00. a. Please see attached Photo Report showing damage. b. Please see attached Specialty Work bid for the confirmation of price.								
21	Chimney_Chimney Flashing & Cap (Bid Item) ADDED BID	1.00	EA	0.00	0.00	772.20	0.00	154.44	**926.64**
	Our line item covers insurance line item 14. We are requesting approval of our full sub bid to replace the chimney flashing and chimney cap. 1. The difference is $106.93. Insurance line item 14 totals $665.27. Our sub bid totals $772.20. a. The chimney has visible cracks and the existing flashing will be fully compromised during the tear-off. The chimney cap requires an upgrade due to the deteriorated condition of the existing unit. Xactimate does not take into account the complexities of this custom chimney work. b. Please see attached Photo Report showing the existing chimney damage and cracking. c. Please see attached Chimney bid for confirmation of price.								
Totals: Dwelling Roof					**11,017.50**	**66,813.76**			**97,264.35**

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
Detached Garage Roof									
22	Tear off, haul and dispose of comp. shingles - Laminated ADJ	9.66	SQ	0.00	0.00	662.10	0.00	132.42	**794.52**
	Our line item covers insurance line item 22. We are requesting 9.66 SQ for tear off, haul and dispose of comp. shingles - Laminated for the detached garage. 1. Per EagleView measured area (no waste applied to tear-off), the correct quantity is 9.66 SQ. Insurance used 8.99 SQ. a. Please see attached EagleView Report confirming the measured square footage for Structure #2.								
23	Laminated - comp. shingle rfg. - w/ out felt ADJ	11.66	SQ	0.00	799.18	3,325.78	274.38	824.99	**5,224.33**
	Our line item covers insurance line item 23. We are requesting 11.66 SQ of Laminated - comp. shingle rfg. - w/out felt for the detached garage. 1. Per EagleView Structure #2, the suggested SQ with 21% waste is 11.66 SQ. Insurance used 11.0 SQ. a. Please see attached EagleView Report for Structure #2 showing the waste calculation of 21% due to the complexity of the roof.								
24	Roofing felt - synthetic underlayment ADJ	11.66	SQ	0.00	0.00	612.97	50.57	122.59	**786.13**
	Our line item covers insurance line item 25. We are requesting 11.66 SQ of roofing felt - synthetic underlayment for the detached garage. 1. Insurance used 8.99 SQ with no waste applied. EagleView suggests 11.66 SQ with 21% waste for Structure #2. a. Roofing felt must be installed in an overlapping pattern requiring cuts at eaves, valleys, hips, and ridges, generating necessary material waste. b. Please see attached EagleView Report confirming the 21% waste calculation for Structure #2.								
25	Asphalt starter - universal starter course ADDED	96.33	LF	0.00	0.00	199.40	16.45	39.88	**255.73**
	The insurance report left out the Starter for the detached garage. We are requesting 96.33 LF of Asphalt starter - universal starter course. 1. Per Xactimate pricing, this costs an additional $199.40. a. Starter is a distinct roofing component with a separate material profile and higher labor rate compared to field shingles. It should not be included in waste calculations as it leads to inaccurate material and labor estimates. b. Please see attached EagleView Report confirming the 96.33 LF eaves measurement for Structure #2.								
26	R&R Hip / Ridge cap - High profile - composition shingles ADJ	78.33	LF	0.00	224.81	673.64	55.58	179.69	**1,133.72**
	Our line item covers insurance line item 24. We are requesting 78.33 LF of R&R Hip / Ridge cap - High profile - composition shingles for the detached garage. 1. Per EagleView Structure #2, ridges = 6.0 LF and hips = 72.33 LF, totaling 78.33 LF. Insurance used 76.1 LF. a. The detached garage has High Profile Ridge cap matching the main house and must be replaced in kind. b. Please see attached EagleView Report confirming the ridge and hip measurements for Structure #2.								
27	R&R Drip edge ADJ	110.50	LF	0.00	99.45	296.14	24.43	79.12	**499.14**

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
	Our line item covers insurance line item 26. We are requesting 110.5 LF of R&R Drip edge for the detached garage. 1. Per EagleView Structure #2, drip edge LF is 110.5 LF. Insurance used 115.58 LF. a. Please see attached EagleView Report confirming the 110.5 LF drip edge measurement for Structure #2.								
28	Step flashing ADDED	5.67	LF	0.00	0.00	69.57	5.74	13.91	**89.22**
	The insurance report left out the Step Flashing for the detached garage. We are requesting 5.67 LF of step flashing. 1. Per Xactimate pricing, this costs an additional $69.57. a. Please see attached EagleView Report confirming the 5.67 LF step flashing measurement for Structure #2. b. Please see Photo Report showing the hail damage to the existing step flashing on the detached garage.								
29	Additional charge for steep roof - greater than 12/12 slope (install) ADDED	11.66	SQ	0.00	0.00	600.84	0.00	120.17	**721.01**
	The insurance report left out the Additional charge for steep roof install for the detached garage. We are requesting 11.66 SQ for the steep roof installation charge. 1. Per Xactimate pricing, this costs an additional $600.84. a. The detached garage pitch per EagleView is 16/12, which exceeds the 12/12 threshold and requires a steep installation charge. Workers must use specialized safety equipment and work at a significantly reduced pace on this slope. b. Please see attached EagleView Report confirming the 16/12 pitch for Structure #2.								
30	Additional charge for steep roof - greater than 12/12 slope (removal) ADDED	9.66	SQ	0.00	155.24	0.00	0.00	31.05	**186.29**
	The insurance report left out the Additional charge for steep roof removal for the detached garage. We are requesting 9.66 SQ for the steep roof removal charge. 1. Per Xactimate pricing, this costs an additional $155.24. a. The detached garage pitch per EagleView is 16/12, requiring additional safety precautions and labor for tear-off beyond standard slope work. b. Please see attached EagleView Report confirming the 16/12 pitch for Structure #2.								
Totals: Detached Garage Roof					**1,278.68**	**6,440.44**			**9,690.09**
Gutters & Downspouts									
31	estimate_2249_Gutter System (Bid Item) ADJ BID	1.00	EA	0.00	0.00	12,297.75	0.00	2,459.55	**14,757.30**

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
	The insurance report does not fully address the gutter system on this property. We are requesting approval of our full sub bid. 1. Our sub bid cost is $12,297.75. a. The property has a specialty gutter system including copper half-round gutters, gutter guards, and custom splash guards that require specialized installation. Xactimate does not take into account the complexities of this bespoke, high-end system. b. The insured recently had the gutters painted and we will be repainting them to restore to pre-loss condition. c. Splash guards are being installed in strategic locations as determined by the property owner to prevent debris buildup, but will not be placed in valley areas where debris accumulation is a concern. d. Please see attached Photo Report showing damage to the gutter system. e. Please see attached estimate_2249 bid for the confirmation of price.								
Totals: Gutters & Downspouts					**0.00**	**12,297.75**			**14,757.30**
Windows									
32	Estimate 8790_Window Replacement (Bid Item) ADDED BID	1.00	EA	0.00	0.00	468.00	0.00	93.60	**561.60**
	The insurance report left out the window replacement scope. We are requesting approval of our sub bid. 1. Our sub bid cost is $468.00. a. Please see attached Photo Report showing damage to the windows. b. Please see attached Estimate 8790 bid for the confirmation of price.								
Totals: Windows					**0.00**	**468.00**			**561.60**
Fence & Siding									
33	Wood Fence_Wood Fence Stain (Bid Item) ADJ BID	1.00	EA	0.00	0.00	7,209.00	0.00	1,441.80	**8,650.80**
	Our line item covers insurance line item 54. We are requesting approval of our full sub bid to power wash and stain the wood fence. 1. The difference is $998.30. Insurance line item 54 totals $6,210.70. Our sub bid totals $7,209.00. a. The hail storm caused damage to the stained finish of the wood fence requiring it to be power washed and restained to restore it to pre-loss condition. b. Please see attached Photo Report showing hail damage to the fence stain finish. c. Please see attached Wood Fence bid for the confirmation of price.								
34	from_Grizzly_Fence__Patio_Fence (Bid Item) ADDED BID	1.00	EA	0.00	0.00	3,254.78	0.00	650.96	**3,905.74**
	The insurance report left out the additional fence scope. We are requesting approval of our sub bid. 1. Our sub bid cost is $3,254.78. a. Please see attached Photo Report showing damage. b. Please see attached Grizzly Fence & Patio bid for the confirmation of price.								
Totals: Fence & Siding					**0.00**	**10,463.78**			**12,556.54**
Debris Removal									

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
35	Dumpster load - Approx. 12 yards, 1-3 tons of debris ADJ	2.00	EA	0.00	0.00	949.66	0.00	189.93	**1,139.59**

Our line item covers insurance line item 58.

We are requesting 2 dumpster loads for this project.

1. The difference is $564.16. Insurance line item 58 totals $385.50 for 1 load. We are requesting $949.66 for 2 loads.

a. Given the total roof area of approximately 85 squares across both the main house and detached garage, plus the steep 16/12 pitch and complexity of the roof system, a single dumpster load is insufficient to contain all tear-off debris.

b. Please see attached Photo Report showing the volume of roofing material on the property.

Totals: Debris Removal					**0.00**	**949.66**			**1,139.59**
General									
36	Residential Supervision / Project Management - per hour ADDED	8.00	HR	0.00	0.00	564.08	0.00	112.82	**676.90**

The insurance report left out Residential Supervision / Project Management.

We are requesting 8.0 HR of project management.

1. Per Xactimate pricing, this costs an additional $564.08.

a. This project involves coordination of multiple trades including roofing, gutters, specialty metalwork, pergola, fencing, painting, and chimney work. A dedicated project manager is required to schedule, sequence, and supervise each trade to ensure code-compliant and quality installation.

b. Insurance restoration projects require additional documentation, inspection scheduling, supplemental negotiations, and warranty coordination beyond standard construction management.

Totals: General					**0.00**	**564.08**			**676.90**
Labor Minimums Applied									
37	Gutter labor minimum ADDED	1.00	EA	0.00	0.00	336.20	0.00	67.24	**403.44**

The insurance report left out the Gutter labor minimum.

We are requesting 1 EA for the gutter labor minimum.

1. Per Xactimate pricing, this costs an additional $336.20.

a. A labor minimum applies when the total gutter scope requires mobilization, setup, and teardown that exceeds the per-linear-foot pricing captured in the gutter line items.

Totals: Labor Minimums Applied					**0.00**	**336.20**			**403.44**
Elevations									
38	Specialty Work_Copper Bay Window (Bid Item) ADJ BID	1.00	EA	0.00	0.00	4,305.60	0.00	861.12	**5,166.72**

Our line item covers insurance line item 18.

We are requesting approval of our full sub bid to replace the Copper Bay Window.

1. Our sub bid cost is $4,305.60.

a. Please see attached Photo Report showing the damage to the copper bay window.

b. Please see attached Specialty Work bid for the confirmation of price.

39	Specialty Work_Porch (Bid Item) ADDED BID	1.00	EA	0.00	0.00	4,134.00	0.00	826.80	**4,960.80**

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
	The insurance report left out the Porch specialty work. We are requesting approval of our sub bid. 1. Our sub bid cost is $4,134.00. a. Please see attached Photo Report showing damage to the porch. b. Please see attached Specialty Work bid for the confirmation of price.								
40	Fo Glass_Window Screen Front Elevation (Bid Item) BID	1.00	EA	0.00	0.00	252.00	0.00	50.40	**302.40**
41	Fo Glass_Window Screen Back Elevation (Bid Item) ADJ BID	1.00	EA	0.00	0.00	468.00	0.00	93.60	**561.60**
	Our line item covers insurance line item 19. We are requesting approval of our full sub bid to replace the window screens on the back elevation. 1. The difference is $216.00. Insurance line item 19 totals $252.00. Our sub bid totals $468.00. a. Please see attached FoGlass bid for the confirmed pricing and scope of window screen replacement. b. Please see attached Photo Report highlighting the hail damage to the window screens.								
42	Ornamental Iron (Bid Item) BID	1.00	EA	0.00	0.00	2,804.06	0.00	560.81	**3,364.87**
43	R&R Tarp - all-purpose poly - per sq ft (labor and material)	400.00	SF	0.00	0.00	532.00	43.89	106.40	**682.29**
Totals: Elevations					**0.00**	**12,495.66**			**15,038.68**
Specialty Structures									
44	Pergola_Pergola Detach Reset & Refinish (Bid Item) ADJ BID	1.00	EA	0.00	0.00	2,457.00	0.00	491.40	**2,948.40**
	Our line item covers insurance line item 56. We are requesting approval of our full sub bid to detach, reset, and refinish the pergola. 1. Our sub bid cost is $2,457.00. a. The pergola is attached to the roof and must be removed to install the new roof system. The top components of the arbor/pergola cannot be reused once removed and must be replaced. Additionally the pergola will be power washed and stained to restore it to pre-loss condition. b. Please see attached Photo Report showing the pergola attachment to the roof and condition of the components. c. Please see attached Pergola bid for the confirmation of price.								
45	Specialty Work_Pillars Power Wash & Stain (Bid Item) ADJ BID	1.00	EA	0.00	0.00	397.80	0.00	79.56	**477.36**
	Our line item covers insurance line item 57. We are requesting approval of our full sub bid to power wash and stain the pillars and corbels. 1. Our sub bid cost is $397.80. a. The hail storm damaged the painted finish on the pillars and corbels requiring them to be power washed and refinished to restore to pre-loss condition. b. Please see attached Photo Report showing the hail damage to the pillars. c. Please see attached Specialty Work bid for the confirmation of price.								
46	Specialty Work_Shutter Power Wash & Stain (Bid Item) ADJ BID	1.00	EA	0.00	0.00	109.20	0.00	21.84	**131.04**

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
	Our line item covers insurance line item 55. We are requesting approval of our full sub bid to power wash and stain the shutters. 1. The difference is $15.12. Insurance line item 55 totals $94.08. Our sub bid totals $109.20. a. The hail storm damaged the painted finish on the shutters requiring them to be power washed and refinished to restore to pre-loss condition. b. Please see attached Photo Report showing the hail damage to the shutters. c. Please see attached Specialty Work bid for the confirmation of price.								
47	Specialty Work_Specialty Work (Bid Item) ADDED BID	1.00	EA	0.00	0.00	538.20	0.00	107.64	**645.84**
	The insurance report left out the Specialty Work scope. We are requesting approval of our sub bid. 1. Our sub bid cost is $538.20. a. Please see attached Photo Report showing damage. b. Please see attached Specialty Work bid for the confirmation of price.								
48	Prime & paint gutter / downspout ADDED	63.00	LF	0.00	0.00	143.01	0.00	28.60	**171.61**
	The insurance report left out the Prime & paint gutter / downspout for the copper half-round gutters on the front of the property. We are requesting 63.0 LF of Prime & paint gutter / downspout. 1. Per Xactimate pricing, this costs an additional $143.01. a. The insured recently had the gutters painted and the copper front gutters must be repainted to restore to pre-loss condition. This line item covers the painting scope not captured by the gutter sub bid. b. Please see attached Photo Report showing the existing painted gutters.								
Totals: Specialty Structures					**0.00**	**3,645.21**			**4,374.25**
Overhead & Profit									
49	Overhead & Profit (20%) ADDED	1.00	EA	0.00	0.00	0.00	0.00	0.00	**0.00**
	For decades we have vetted, managed, trained and warrantied subcontractors for roofing, gutters, painting, fencing, siding etc. due to storm restoration in the DFW area. We charge a minimum 20% overhead and profit above the subcontractors cost as we act as the single point of contact for all subcontractors' trade complexities, plus cover all their liability and warranty for our clients. Project Requires General Contracting This project involves coordination of multiple trades—including roofing, gutter replacement, exterior painting, window screen repair, specialty metalwork, chimney, fencing, pergola, and pillar restoration. Per industry standards and Xactimate guidelines, O&P is warranted whenever three or more trades are involved and coordinated by a general contractor. Complex Scheduling and Management Each trade must be scheduled in the correct sequence, managed for quality and timing, and supervised for code compliance and safety. This requires administrative staff, project managers, and dedicated personnel which all reside at our physical office—all part of our company's operational infrastructure. We Are Not a Single-Trade Contractor Unlike subcontractors, we do not perform only one scope of work. We maintain a physical office, estimators, coordinators, insurance claim specialists, and field supervisors. These are all actual employees of IFC Contracting Solutions—these employees are the overhead which is built into O&P. These costs are necessary to support project execution, client communication, and warranty management. Insurance Restoration Demands Administrative Oversight Insurance jobs require extra documentation, invoicing, inspection scheduling, supplemental negotiation, and warranty coordination, all of which involve personnel beyond the jobsite. These employees reside at our physical location and work to adhere to the highest construction standards. This is not reimbursed in trade line items and is accounted for within O&P.								

#	DESCRIPTION	QTY	UNIT	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
Totals: Overhead & Profit					**0.00**	**0.00**			**0.00**

IFC Contracting Solutions

Line Item Totals

Line Item Total: ISBELL_CHRIS	**$126,770.72**
Material Sales Tax (8.25%)	**$4,337.88**
Replacement Cost Value	**$156,462.74**

Coverage Summary

Coverage	Item Total	%	ACV Total	%
Dwelling	$134,216.11	85.78%	$134,216.11	85.78%
Other Structures	$22,246.63	14.22%	$22,246.63	14.22%
Total	**$156,462.74**	**100.00%**	**$156,462.74**	**100.00%**

Summary for Dwelling

Line Item Total	**$134,216.11**
Material Sales Tax	**$3,910.73**
Replacement Cost Value	**$134,216.11**
Net Claim	**$134,216.11**

Summary for Other Structures

Line Item Total	**$22,246.63**
Material Sales Tax	**$427.15**
Replacement Cost Value	**$22,246.63**
Net Claim	**$22,246.63**

Recap of Taxes, Overhead and Profit

Item	Overhead (10%)	Profit (10%)	Material Sales Tax (8.25%)	Manuf. Home Tax (5%)
Line Items	$12,677.07	$12,677.07	$4,337.88	0.00
Total	**$12,677.07**	**$12,677.07**	**$4,337.88**	**0.00**

Recap by Room

Estimate: ISBELL_CHRIS

Section	Subtotal	%
Dwelling Roof	$97,264.35	62.16%
Coverage: Dwelling 62.16% = $97,264.35		
Detached Garage Roof	$9,690.09	6.19%
Coverage: Other Structures 6.19% = $9,690.09		
Gutters & Downspouts	$14,757.30	9.43%
Coverage: Dwelling 9.43% = $14,757.30		
Windows	$561.60	0.36%
Coverage: Dwelling 0.36% = $561.60		
Fence & Siding	$12,556.54	8.03%
Coverage: Other Structures 8.03% = $12,556.54		
Debris Removal	$1,139.59	0.73%
Coverage: Dwelling 0.73% = $1,139.59		
General	$676.90	0.43%
Coverage: Dwelling 0.43% = $676.90		
Labor Minimums Applied	$403.44	0.26%
Coverage: Dwelling 0.26% = $403.44		
Elevations	$15,038.68	9.61%
Coverage: Dwelling 9.61% = $15,038.68		
Specialty Structures	$4,374.25	2.80%
Coverage: Dwelling 2.80% = $4,374.25		
Overhead & Profit	$0.00	0.00%
Coverage: Dwelling 0.00% = $0.00		
Subtotal of Areas	**$156,462.74**	**100.00%**
Coverage: Dwelling 85.78% = $134,216.11		
Coverage: Other Structures 14.22% = $22,246.63		
Total	**$156,462.74**	**100.00%**

Recap by Category

Category	O&P Items Total	%
ROOFING	$96,633.94	61.76%
GENERAL	$16,821.11	10.75%
FENCING	$15,921.41	10.18%
SOFFIT, FASCIA, & GUTTER	$15,332.35	9.80%
WINDOWS & DOORS	$6,592.32	4.21%
SPECIALTY ITEMS	$2,948.40	1.88%
GENERAL DEMOLITION	$1,139.59	0.73%
PAINTING	$1,073.62	0.69%
O&P Items Subtotal	**$152,124.86**	**97.23%**
Material Sales Tax	$4,337.88	2.77%
Overhead	$12,677.07	8.10%
Profit	$12,677.07	8.10%
Total	**$156,462.74**	**100.00%**